

UPDATE ON TOLL MILLING PROGRESS

Highlights

- Excellent progress towards mining and Toll Milling readiness at Hualilan.
- Final open pit mine design and mining schedules for Toll Milling pits completed.
- 10% increase in grade with the Schedule now entirely based on Indicated Resources.
- Initial 150,000t of material mined averages 8.7 g/t Au and 34.5 g/t Ag.
- Schedule delivers over 90,000t of toll milling material in first 3 months of mining.
- Enhanced operational flexibility as only 3 out of 4 potential pits are required.
- Mining schedule completion enables finalisation of contract mining and toll material haulage contracts.
- Toll Mill plant refurbishment commenced with equipment repairs in progress following the receipt of required funds from a local bank in Argentina in late December 2024.
- Pre-Feasibility Study ("PFS") for Toll Milling on schedule for completion in March 2025.

Kris Knauer the Managing Director of Challenger Gold commented:

"We are making excellent progress towards being mining and Toll Milling ready with all key workstreams on schedule.

The completion of Toll Milling pit design and mining schedules is a significant milestone as it allows us to finalise quotes for contract mining and trucking of material to Casposo.

The final mining schedule for tolling itself represents a significant improvement over our initial case. It shows a 10% improvement in grade; delivers 6-months toll milling feed in the first 3-months of mining; front loads cashflows with grades of 8.7 g/t Au and 34.5/t Ag during the first year of tolling and provides significant flexibility and optionality with only 3 of the 4 pits required and an additional 120,000 of toll milling material available in the toll milling pits.

Finally, Austral Gold, the Toll Mill operator, has indicated that refurbishment of the Casposo Plant is progressing."



Challenger Gold (ASX: **CEL**) ("**CEL**" or the "**Company**") is pleased to provide an update on its progress towards the commencement of Toll Milling, following the successful completion of definitive Toll Milling Agreements, and a Strategic Placement on January 11, 2025.

Completion towards Mining and Toll Milling readiness at Hualilan

The status of the key workstreams for mining and Toll Milling readiness and the PFS is outlined below:

- Geology, Pit Optimisation, Mine Design and Scheduling:
 - Geology and Resource Analysis Completed.
 - **Toll Mill Pit Design Completed.** A site visit in early January 2025 led to design improvements, increasing the contained mineralisation and adding operational flexibility.




Figure 1 - 3D view of Hualilan showing Toll Milling pits and site layout



- Mining Schedules Completed. The schedule optimises the delivery of high-grade mineralisation, frontloading material grading 8.7 g/t Au, 34.5 g/t Ag in the first year. A 3 to 6-month stockpile buffer is maintained through toll milling, providing further operational flexibility and security. Only three of the four initial toll milling pits were required reducing reliance on any single pit while preserving optionality for additional tolling feed.
- Geotechnical Work & Pit Design Approval Completed.
- Processing, Metallurgy and Process Operational Expenditure ("OPEX"):
 - Metallurgical Test Work In Progress. Completed gravity, leach, and solid-liquid separation testing for a composite sample representative of mineralisation across the toll milling pits, with results pending. A variability testing program (~10 samples per toll milling pit), is underway and expected to be completed by end of February 2025.
 - Processing Cost Model In Progress. Work continuing in conjunction with Casposo plant; completion expected following receipt of final program of metallurgical testwork in February 2025.
- Mining Capital Expenditure ("CAPEX") and OPEX models:
 - Contractor Mining Option In Progress. Responses received to Requests for Information ("RFI") for open pit drill, blast, load, and haul. Requests for Quote ("RFQ") being issued based on the finalised mining schedule.
 - Owner-Operator (Hire) Option In Progress. Responses received to RFIs for open pit load and haul equipment hire. RFQs issued based on the finalised mining schedule.
 - Owner-Operator (Buy) Option Completed. Responses received to RFQs for open pit load and haul equipment purchase CAPEX and OPEX. Preferred vendor selected for purchase.
 - Owner-Operator Maintenance In Progress. RFQs issued to Original Equipment
 Manufacturer ("OEM") Maintenance and Repair Contract ("MARC"). Responses expected
 shortly.
 - Drill and Blast Rock-on-Ground ("ROG") Contractor Completed. Responses received to RFQs. Preferred vendor selected.
 - Road Transport Costs In Progress. Responses received to RFIs for haulage between Hualilan and Casposo. RFQs issue, pending final transport route selection.
- Labor Cost Model Completed. Final adjustments pending Contractor vs. Owner-Operator selection.
 - Technical and Management Team: 23 required for contract mining case including 12 to be transferred from existing exploration team.
 - Mine Operations Team (owner operator options): 23 additional roles.

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director



 Economic Model – In Progress. Completed, with final minor input adjustments pending the aforementioned factors.

Toll Milling Startup Pre-Feasibility Study

CEL previously announced plans to release a Scoping Study focused on the Toll Milling startup. However, following discussions with lead consultants, it has been determined that, given the substantial work already completed, the study will be advanced directly to PFS level.

The PFS will be prepared in accordance with both Australian Joint Ore Reserves Committee ("JORC") and Canadian NI 43-101 standards. A key distinction between the two reporting frameworks is that a PFS under NI 43-101 excludes inferred resources from the mine plan and requires independent Qualified Person ("QP") sign-off. In contrast, JORC does not require independence for Competent Persons ("CP").

CEL has engaged the following consultants to complete the PFS:

- Ausenco (Australia) Metallurgy, Mineral Processing, and Processing Costs.
- Fuse Advisors (Canada) Mining, Infrastructure, Capital and Mining Costs, and Economic Analysis.
- Mining Plus (Australia) Project Background, Geology, and Resource Estimation.
- Micromine (Canada) Open Pit Scheduling.
- PHC Consulting (Canada) Geotechnical Studies.

Various San Juan, Argentina, based consultants have been engaged to assist with Environmental Studies, Permitting, and Social & Community Engagement.

Finally, Whittle Consulting has completed an optimisation of the Toll Milling pits, as part of the broader Enterprise Optimisation Study for the standalone Hualilan full-scale study, with this Enterprise Optimisation Study nearing completion.

Updated Toll Milling Pit Designs

Initially, the Company planned to develop four small toll milling pits - Sanchez, Norte, Magnata, and Sentazon - based on optimization studies conducted in collaboration with Whittle Consulting. These pits were selected considering grade, strip ratio, and site accessibility.

Following a strategic review and an on-site assessment by the lead mining and geotechnical consultants, it was determined that the Toll Milling objectives could be fully met using only three pits—Sanchez, Norte, and Magnata. As a result, Sentazon has been held in reserve, providing operational flexibility and an opportunity for additional toll milling, if required.



The key metrics for the three selected pits are as follows (see Table 1):

- Total Mineralised Material: 450 kt.
- Average Grade: 6.7 g/t Au and 39.7 g/t Ag, containing 97.2 koz Au and 575 koz Ag.
- Strip Ratio: 5.9 with 2,652 Mt of waste, inclusive of material stockpiled for the Hualilan full-scale project.

The Sentazon pit and inferred material in the other pits, not included in the schedule contains:

- 119 kt of additional mineralised material (mix of Indicated and Inferred refer Table 1).
- Grade: 5.7 g/t Au and 32.9 g/t Ag.
- Contained metal: 19.0 koz Au and 123 koz Ag.
- Strip Ratio: 6.6.




Figure 2 - Toll Milling Site Layout



Material Strip Ratio Au Ag **Au Contained Ag Contained** Mineralisation (g/t) (g/t (oz) (oz) Sanchez Pit - Indicated 93,423 7.53 12.97 22,613 38,952 1.4 Norte Pit - Indicated 130,433 9.06 51.78 37,992 217,134 5.2 Magnata Pit - Indicated 227,100 5.01 43.74 36,567 319,391 8.1 Sentazon Pit -Indicated 60,343 5.73 32.87 11,107 63,766 6.6 511,299 6.59 38.89 108,280 639,242 **Total Indicated category** Sanchez Pit - Inferred 8.40 17.70 159 91 Norte Pit - Inferred 44,991 Magnata Pit - Inferred 4.58 28.61 6,628 41,384 2.70 40.31 Sentazon Pit - Inferred 13,593 1,182 17,618 **Total Inferred category** 58,743 4.16 31.29 7,852 59,092 Total 6.34 38.10 116,132 698,334 570,041

Table 1 - Mineralisation within the final designed Toll milling pits

Toll Milling Pit Mine Schedule

The pit selection and mine schedule were developed incorporating the following key considerations:

- Target Production: 450 kt of mineralised material, with a minimum annual throughput of 150 kt.
- Dilution assumptions (5%) and mining recovery estimates (95%) applied, reflecting mineralisation characteristics and selective mining methods.
- Resource Classification:
 - All Inferred material is excluded from Toll Milling feed and stockpiled for future processing in the Hualilan Full-Scale project.
 - Material suitable for future Hualilan Full-Scale processing is stockpiled separately rather than directed to waste dumps. This is ignored in the below physical summaries.
- Early Start Strategy:
 - The initial mining phase prioritises shallow mineralised material, minimising the lead time for mining commencement before toll milling.
 - Aspirational goal of delivering 75 kt of mineralised material in the first three months.
- Operational Efficiency:
 - Designed to maintain steady-state production, ensuring consistent equipment utilisation, and to ensure attractiveness for mining contractors.
 - Stockpile buffer maintained to enable continuous toll milling operations without disrupting mining efficiency.
- Infrastructure Development: waste material to be repurposed for constructing mine access and pioneering routes, facilitating high productivity pioneering for the Hualilan Full-Scale project.



- Workforce & Shift Optimisation: evaluating both day-shift-only mining (to reduce labor demands) and 24/7 operations.
- Owner-Operator (Buy Option) Equipment Selection: equipment chosen for the owneroperator model will be appropriately sized for long-term Hualilan Full-Scale operations, while still allowing for selective mining during the toll milling phase.

Table 2 - Final Toll Mill Scheduled Open Pit Physicals (6-month intervals)

Open Pit	Y1 H1	Y1-H2	Y2-H1	Y2-H2	Y3-H1	Y3-H2	Total/Avg
Toll milling material mined	126,916	96,940	74,231	41,521	52,138	59,211	450,957
Au (g/t)	8.50	7.38	5.06	3.91	5.15	4.67	6.4
Ag (g/t)	28.76	40.61	39.56	37.73	40.87	47.75	37.8
AuEq (g/t)	8.8	7.8	5.5	4.3	5.6	5.2	6.8
Total material mined (t)	526,885	535,618	526,885	535,618	529.796	450,462	3,105,264

This final Pit Schedule is shown in Table 2. The schedule contains 450,957t at a grade of 6.4 g/t Au and 37.8 g/t Ag containing 92,500 oz gold and 548,000 oz Ag.

This represents a 10% grade increase which will significantly improve the toll milling outcome.

The schedule front loads higher grade material with the result that processed grades will be 8.7 g/t Au and 34.5 g/t Ag for the first year of tolling. Additionally, it delivers over 90,000t of toll milling material in the first 3-months of mining and 224,000t in the first 12 months.

This creates a 3 to 6-month stockpile buffer which is maintained through toll milling, providing further operational flexibility and security.

The Company remains focused on delivering a robust Pre-Feasibility Study and advancing towards Toll Milling operations in an efficient and timely manner. Further updates will be provided as key milestones are achieved.

This ASX release was approved by the Board of Directors.

For further information contact:

Kris KnauerSergio RotondoMedia EnquiriesManaging DirectorChairmanJane Morgan+61 411 885 979+1 646 462 9273+ 61 405 555 618

kris.knauer@challengerex.com sergio.rotondo@challengerex.com jm@janemorganmanagement.com.au



Previous announcements referred to in this release include:

The Mineral Resource Estimate for the Hualilan Gold Project was first announced to the ASX on 1 June 2022 and updated 29 March 2023. The Mineral Resource Estimate for the El Guayabo Project was first announced to the ASX on 14 June 2023. The Company confirms it is not aware of any information or assumptions that materially impacts the information included in that announcement and that the material assumptions and technical parameters underpinning the Mineral Resource Estimate continue to apply and have not materially changed.

ADDITIONAL INFORMATION

COMPETENT PERSON STATEMENT – EXPLORATION RESULTS AND MINERAL RESOURCES

The information that relates to sampling techniques and data, exploration results, geological interpretation and Mineral Resource Estimate has been compiled Dr Stuart Munroe, BSc (Hons), PhD (Structural Geology), GDip (AppFin&Inv) who is a full-time employee of the Company. Dr Munroe is a Member of the AusIMM. Dr Munroe has over 20 years experience in the mining and metals industry and qualifies as a Competent Person as defined in the JORC Code (2012).

Dr Munroe has sufficient experience of relevance to the styles of mineralisation and the types of deposits under consideration, and to the activities undertaken, to qualify as a Competent Person as defined in the 2012 Edition of the Joint Ore Reserves Committee (JORC) Australasian Code for Reporting of Exploration Results and Mineral Resources. Dr Munroe consents to the inclusion in this report of the matters based on information in the form and context in which it appears. The Australian Securities Exchange has not reviewed and does not accept responsibility for the accuracy or adequacy of this release.

FORWARD LOOKING STATEMENTS

The announcement may contain certain forward-looking statements. Words 'anticipate', 'believe', 'expect', 'forecast', 'estimate', 'likely', 'intend', 'should', 'could', 'may', 'target', 'plan', 'potential' and other similar expressions are intended to identify forward-looking statements. Indication of, and guidance on, future costings, earnings and financial position and performance are also forward-looking statements.

Such forward looking statements are not guarantees of future performance, and involve known and unknown risks, uncertainties and other factors, many of which are beyond the control of Challenger Gold Ltd, its officers, employees, agents and associates, which may cause actual results to differ materially from those expressed of implied in such forward-looking statements. Actual results, performance, or outcomes may differ materially from any projections or forward-looking statements or the assumptions on which those statements are based.

You should not place any undue reliance on forward-looking statements and neither. Challenger nor its directors, officers, employees, servants or agents assume any responsibility to update such information. The stated Production Targets are based on the Company's current expectations of future results or events and should not be relied upon by investors when making investment decisions. Further evaluation work and appropriate studies are required to establish sufficient confidence that this target will be met.

Financial numbers, unless stated as final, are provisional and subject to change when final grades, weight and pricing are agreed under the terms of the offtake agreement. Figures in this announcement may not sum due to rounding.

The Company confirms that it is not aware of any new information or data that materially affects the information included in the original market announcements and that all material assumptions and technical parameters underpinning the estimates in the relevant original market announcements continue to apply and have not materially changed. The Company confirms that the form and context in which the Competent Person's findings are presented have not been materially modified from the original market announcements.



HUALILAN GOLD PROJECT MRE AND SCOPING STUDY

All references to the Scoping Study and its outcomes in this announcement relate to the ASX Announcement of 8 November 2023 'Hualilan Gold Project Scoping Study'. Please refer to that announcement for full details and supporting documentation.

Table 2: Hualilan Hold Project Mineral Resource Estimate (March 2023)

Domain	Category	Mt	Au (g/t)	Ag (g/t)	Zn (%)	Pb (%)	AuEq (g/t)	AuEq (Mozs)
US\$1800 optimised shell > 0.30 ppm AuEq	Indicated	45.5	1.0	5.1	0.38	0.06	1.3	1.9
	Inferred	9.6	1.1	7.3	0.43	0.06	1.4	0.44
Below US\$1800 shell >1.0ppm AuEq	Indicated	2.7	2.0	9.0	0.89	0.05	2.5	0.22
	Inferred	2.8	2.1	12.4	1.1	0.07	2.8	0.24
Total		60.6	1.1	6.0	0.4	0.06	1.4	2.8

Note: Some rounding errors may be present

¹ Gold Equivalent (AuEq) values - Requirements under the JORC Code

- $\bullet \qquad \text{Assumed commodity prices for the calculation of AuEq is Au US$1900 Oz, Ag US$24 Oz, Zn US$4,000/t, Pb US$2000/t}\\$
- Metallurgical recoveries are estimated to be Au (95%), Ag (91%), Zn (67%) Pb (58%) across all ore types (see JORC Table 1 Section 3 Metallurgical assumptions) based on metallurgical test work.
- The formula used: $AuEq (g/t) = Au (g/t) + [Ag (g/t) \times 0.012106] + [Zn (%) \times 0.46204] + [Pb (%) \times 0.19961]$
- CEL confirms that it is the Company's opinion that all the elements included in the metal equivalents calculation have a reasonable potential to be recovered and sold.

JORC Code, 2012 Edition – Table 1 report template Section 1 Sampling Techniques and Data -Hualilan Project

(Criteria in this section apply to all succeeding sections.)

Cri	Ter	la 💮	
911	LEI		

JORC Code explanation

Sampling techniques

- Nature and quality of sampling (eg cut channels, random chips, or specific specialised industry standard measurement tools appropriate to the minerals under investigation, such as down hole gamma sondes, or handheld XRF instruments, etc). These examples should not be taken as limiting the broad meaning of sampling.
- Include reference to measures taken to ensure sample representivity and the appropriate calibration of any measurement tools or systems used.
- Aspects of the determination of mineralisation that are Material to the Public Report.
- In cases where 'industry standard' work has been done this would be relatively simple (eg 'reverse circulation drilling was used to obtain 1 m samples from which 3 kg was pulverised to produce a 30 g charge for fire assay'). In other cases, more explanation may be required, such as where there is coarse gold that has inherent sampling problems. Unusual commodities or mineralisation types (eg submarine nodules) may warrant disclosure of detailed information.

Commentary

Diamond core (HQ3 and NQ3) was cut longitudinally on site using a diamond saw or split using a hand operated hydraulic core sampling splitter. Samples lengths are generally from 0.5m to 2.0m in length (average 1.74m). Sample lengths are selected according to lithology, alteration, and mineralization contacts.

For reverse circulation (RC) drilling, 2-4 kg sub-samples from each 1m drilled were collected from a face sample recovery cyclone mounted on the drill machine.

Channel samples are cut into underground or surface outcrop using a hand-held diamond edged cutting tool. Parallel saw cuts 3-5cm apart are cut 2-4cm deep into the rock which allows for the extraction of a representative sample using a hammer and chisel. The sample is collected onto a plastic mat and collected into a sample bag.

Core, RC and channel samples were crushed to approximately 85% passing 2mm. A 500g or a 1 kg sub-sample was taken and pulverized to 85% passing 75 μ m. A 50g charge was analysed for Au by fire assay with AA determination. Where the fire assay grade is > 10 g/t gold, a 50g charge was analysed for Au by Fire assay with gravimetric determination.

A 10g charge was analysed for at least 48 elements by 4-acid digest and ICP-MS determination. Elements determined include Ag, As, Ba, Be, Bi, Ca, Ce, Co, Cr, Cs, Cu, Fe, Ga, Ge, Hf, In, K, La, Li, Mg, Mn, Mo, Na, Nb, Ni, P, Pb, Rb, Re, S, Sb Sc, Se, Sn, Sr, Ta, Te, Th, Ti, Tl, U, V, W, Y, Zn and Zr.

For Ag > 100 g/t, Zn, Pb and Cu > 10,000 ppm and S > 10%, overlimit analysis was done by the same method using a different calibration.

Unused pulps are returned from the laboratory to the Project and stored in a secure location, so they are available for any further analyses. Remaining drill core is stored undercover for future use if required.

Visible gold observed has been observed in only 1 drill core sample only. Coarse gold is not likely to result in sample bias.

Historic Data:

There is little information provided by previous explorers to detail sampling techniques. Selected drill core was cut with a diamond saw longitudinally and one half submitted for assay. Assay was generally done for Au. In some drill campaigns, Ag and Zn were also analysed. There is limited multielement data available. No information is available for RC drill techniques and sampling.

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

JORC Code explanation Criteria Commentary **Drilling techniques** Drill type (eg core, reverse circulation, open-hole hammer, rotary air blast, auger, Bangka, sonic, etc) and details (ea core diameter, triple or standard tube, depth of diamond tails, facesampling bit or other type, whether core is oriented and if so, by what method, etc). collar surveys. Historic Data: Method of recording and Drill sample recovery assessing core and chip sample recoveries and results assessed. Measures taken to maximise sample recovery and ensure representative nature of the samples. Of the remaining 202,139.30 metres of bedrock drilled, core recovery is 96.8%. Whether a relationship exists between sample recovery and grade and whether sample bias may have occurred due to preferential loss/gain of fine/coarse material.

CEL drilling of HQ3 core (triple tube) was done using various truck and track mounted drill machines that are operated by various drilling contractors based in Mendoza and San Juan. The core has not been oriented as the rock is commonly too broken to allow accurate core orientation.

CEL drilling of reverse circulation (RC) drill holes was done using a track-mounted LM650 universal drill rig set up for reverse circulation drilling. Drilling was done using a 5.25 inch hammer bit.

Collar details for historic drill holes, DD drill holes, RC drill holes completed by CEL that are used in the resource estimate are detailed in CEL ASX releases:

1 June 2022 (Maiden MRE): https://announcements.asx.com.au/asxpdf/20220601/pdf/459jfk8q7x2mty.pdf and 29 March 2023 (MRE update):

https://announcements.asx.com.au/asxpdf/20230329/pdf/45n49jlm02grm1.pdf

Collar locations for drill holes are surveyed using DGPS. Three DD holes and 3 RC holes have hand-held GPS

Historic drill hole data is archival, data cross checked with drill logs and available plans and sections where available. Collar locations have been checked by CEL using differential GPS (DGPS) to verify if the site coincides with a marked collar, tagged drill site or likely drill pad location. In most cases the drill collars coincide with historic drill site, some of which (but not all) are tagged. The collar check surveys were reported in POSGAR (2007) projection and converted to WGS84.

Drill core is placed into wooden boxes by the drillers and depth marks are indicated on wooden blocks at the end of each run. These depths are reconciled by CEL geologists when measuring core recovery and assessing core loss. Triple tube drilling has been being done by CEL to maximise core recovery.

- 761 CEL diamond drill holes completed have been used for the CEL resource estimate. Some of these holes are located outside the resource area.
 - Total drilled is 224,180.60 metres, including cover drilled of 22,041.30 metres (9.8 %).

RC sub-samples are collected from a rotary splitter mounted to the face sample recovery cyclone. A 2-4 kg subsamples is collected for each metre of RC drilling. Duplicate samples are taken at the rate of I every 25-30 samples using a riffle splitter to split out a 2-4 kg sub-sample. The whole sample recovered is weighed to measure sample recovery and consistency in sampling.

37 CEL RC drill holes have been used in the CEL resource estimate. Total metres drilled is 2,923m. Cover drilled is 511 m (17.5%)

Channel samples have been weighed to ensure a consistency between sample lengths and weights. The channel samples are collected from saw-cut channels and the whole sample is collected for analysis. There is no correlation between sample length and assay values.

193 surface and underground channels have been used in the CEL resource estimate.

Challenger Gold Limited ACN 123 591 382 ASX: CEL

Issued Capital 1.688m shares 126.7m options 50.5m perf rights **Australian Registered Office** Level 1 100 Havelock Street

West Perth WA 6005

Directors Mr Kris Knauer, MD and CEO Mr Sergio Rotondo, Chairman Dr Sonia Delgado, Exec. Director Mr Fletcher Quinn, Non-Exec. Director Mr Pini Althaus, Non Exec Director Mr Brett Hackett Non Exec Director


Criteria	JORC Code explanation	Commentary
		Channels total 2597.70 metres in length. The average weight per metre sampled is 3.7 kg/m which is adequate for the rock being sampled and compares well with the expected weight for ½ cut HQ3 drill core of 4.1 kg/m. A possible relationship has been observed in historic drilling between sample recovery and Au Ag or Zn values whereby low recoveries have resulted lower reported values. Historic core recovery data is incomplete. Core recovery is influenced by the intensity of natural fracturing in the rock. A positive correlation between recovery and RQD has been observed. The fracturing is generally post mineral and not directly associated with the mineralisation.
Logging	 Whether core and chip samples have been geologically and geotechnically logged to a level of detail to support appropriate Mineral Resource estimation mining studies and metallurgical studies. Whether logging is qualitative or quantitative in nature. Core (or costean channel etc) photography. The total length and percentage of the relevant intersections logged. 	For CEL drilling, all the core (100%) is photographed and logged for recovery, RQD, weathering, lithology, alteration, mineralization, and structure to a level that is suitable for geological modelling, Mineral Resource Estimation and metallurgical test work. RC drill chips are logged for geology, alteration and mineralisation to a level that is suitable for geological modelling resource estimation and metallurgical test work. Where possible logging is quantitative. Geological logging is done into MS Excel in a format that can readily be cross-checked and is back-up transferred to a secure, offsite, cloud-based database which holds all drill hole logging sample and assay data. No specialist geotechnical logging has been undertaken. Detailed logs are available for most of the historical drilling. Some logs have not been recovered. No core photographs from the historic drilling have been found. No drill core has survived due to poor storage and neglect. No historic RC sample chips have been found.
Sub-sampling techniques and sample preparation	 If core whether cut or sawn and whether quarter half or all core taken. If non-core whether riffled tube sampled rotary split etc and whether sampled wet or dry. For all sample types the nature quality and appropriateness of the sample preparation technique. Quality control procedures adopted for all sub-sampling stages to maximise representivity of samples. Measures taken to ensure that the sampling is representative of 	CEL samples have been submitted to the MSA laboratory in San Juan, the ALS laboratory in Mendoza and the former SGS laboratory in San Juan for sample preparation. The sample preparation technique is considered appropriate for the style of mineralization present in the Project. Sample sizes are appropriate for the mineralisation style and grain size of the deposit. Sample intervals are selected based on lithology, alteration, and mineralization boundaries. Representative samples of all of the core are selected. Sample length averages 1.74m. Second-half core or ¼ core samples have been submitted for a mineralised interval in 1 drill hole only and for some metallurgical samples. The second half of the core samples has been retained in the core trays for future reference. Competent drill core is cut longitudinally using a diamond saw for sampling of ½ the core. Softer core is split using a wide blade chisel or a manual core split press. The geologist logging the core, marks where the saw cut or split is to be made to ensure half-core sample representivity. From GNDD073 and later holes, duplicate core samples consisting of two ¼ core samples over the same interval have been collected approximately every 30-50m drilled.

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

JORC Code explanation Criteria Commentary Duplicate core sample results and correlation plots (log scale for Au, Ag, Zn, Pb, Fe and S) are shown below: the in-situ material collected including for instance results for RSQ mean median variance field duplicate/second-half count sampling. duplicate original duplicate original duplicate original Whether sample sizes are Au (ppm) 3,523 0.960 0.076 0.077 0.007 0.006 0.640 0.816 appropriate to the grain size of Ag (ppm) 3,523 0.696 0.53 0.48 0.17 0.16 7.99 3.55 the material being sampled. 3,523 0.08 Cd (ppm) 0.979 1.34 1.26 0.08 160.63 144.11 3,523 0.451 13.85 3.30 4.3E+03 2.5E+03 Cu (ppm) 14.84 3.40 Fe (%) 3,523 0.990 1.997 1.996 1.700 1.710 3.74 3.75 Pb (ppm) 3,523 0.940 64.7 62.4 13.7 13.4 1.9E+05 2.7E+05 3.523 0.973 0.330 0.140 0.140 0.332 S (%) 0.333 0.346 72 Zn (ppm) 3.523 0.976 254 243 73 3.8.E+06 3.5.E+06 RSQ = R squared Hualilan DD - Duplicate Samples - Au (ppm) Hualilan DD - Duplicate Samples - Ag (ppm) Hualilan DD - Duplicate Samples - Zn (ppm) 1000 100000 100 10000 1000 0.01 0.001 0.001 0.1 10 100 0.1 10 100 0.001 0.001 100 1000 10000 100000 Au (ppm) Original Ag (ppm) Original Zn (ppm) Original

Challenger Gold Limited ACN 123 591 382 ASX: CEL

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director




RC sub-samples over 1m intervals are collected at the drill site from a cyclone mounted on the drill rig. A duplicate RC sample is collected for every 25-30m drilled.

The duplicate RC sample results and correlation plots (log scale for Au, Ag, Zn, Pb, Fe and S) are shown below:

	count	RSQ	m	ean	me	dian	varia	ance
			original	duplicate	original	duplicate	original	duplicate
Au (ppm)	85	0.799	0.101	0.140	0.017	0.016	0.041	0.115
Ag (ppm)	85	0.691	1.74	2.43	0.59	0.58	13.59	64.29
Cd (ppm)	85	0.989	15.51	16.34	0.41	0.44	4189	4737
Cu (ppm)	85	0.975	47.74	53.86	5.80	5.70	2.4E+04	3.1E+04
Fe (%)	85	0.997	1.470	1.503	0.450	0.410	7.6	7.6
Pb (ppm)	85	0.887	296.0	350.6	26.3	32.4	6.0E+05	7.4E+05
S (%)	85	0.972	0.113	0.126	0.020	0.020	0.046	0.062
Zn (ppm)	85	0.977	3399	3234	158	177	2.5.E+08	2.1.E+08
RSQ = R squ	ıared							

Challenger Gold Limited ACN 123 591 382 ASX: CEL

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director



Issued Capital 1,688m shares 126.7m options 50.5m perf rights **Australian Registered Office** Level 1 100 Havelock Street

West Perth WA 6005

Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

riteria	JORC Code explanation	Commentary	,								
		Fe (%)	45	0.428	4.266	5.745	1.390	1.560	44.4	107.0	
		Pb (ppm)	45	0.007	955.4	3776.0	75.3	60.7	3.5E+06	3.0E+08	
		S (%)	45	0.908	1.307	1.432	0.040	0.030	14.294	16.234	
		Zn (ppm)	45	0.509	15117	12684	1300	763	8.8.E+08	5.2.E+08	
		Hualilan Chann 100 10 popicione 1 on (bbb) 0.1	el - Duplicate	e Samples - Au (p		1000 100 100 100 100 100 100 100 100 10	el - Duplicate Samples -	•	100000 100000 10000 10000 1000 1000 10	Channel - Duplicate San	nples - Zn (ppm
		0.001	Au (ppm) C	1 10 Priginal			0.1 1 Ag (ppm) Original el - Duplicate Samples -			10 100 10 Zn (ppm) Origina Channel - Duplicate Sa	ıl
		10	•	·.	•	1000	•	: *	10		

Quality of assay data and laboratory tests

The nature quality and appropriateness of the assaying and laboratory procedures used and whether the technique is

The MSA laboratory used for sample preparation in San Juan was inspected by Stuart Munroe (Exploration Manager) and Sergio Rotondo (CEL Director) prior to any samples being submitted. The laboratory has been visited and revied most recently by Stuart Munroe (Exploration Manager) in May 2022. The laboratory procedures are consistent with international best practice and are suitable for samples from the Project. The SGS laboratory in San Juan and the ALS laboratory in Mendoza has not yet been inspected by CEL

100

Pb (ppm) Original

1000

10000

0.001

0.001

0.01

0.1

S (pct) Original

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street

West Perth WA 6005

0.01

0.01

0.1

Fe (pct) Original

Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

100

Criteria


JORC Code explanation

- tion Commentary
- considered partial or total.

 For geophysical tools
 spectrometers handheld XRF
 instruments etc the parameters
 used in determining the analysis
 including instrument make and
 model reading times calibrations
 factors applied and their
 derivation etc.
- Nature of quality control procedures adopted (eg standards blanks duplicates external laboratory checks) and whether acceptable levels of accuracy (i.e. lack of bias) and precision have been established.

representatives due to COVID-19 restrictions. Each laboratory presents internal laboratory standards for each job to gauge precision and accuracy of assays reported.

CEL have used two different blank samples, submitted with drill core and subjected to the same preparation and assay as the core samples, RC sub-samples and channel samples. The blank samples are sourced from surface gravels in the Las Flores area of San Juan and from a commercial dolomite quarry near San Juan. In both cases the blank material is commonly for construction. Commonly, the blank samples are strategically placed in the sample sequence immediately after samples that were suspected of containing higher grade Au, Ag, S or base metals to test the lab preparation and contamination procedures. The values received from the blank samples suggest only rare cross contamination of samples during sample preparation.




For GNDD001 – GNDD010 samples analysed by MSA in 2019, three different Certified Standard Reference pulp samples (CRM) with known values for Au Ag Pb Cu and Zn were submitted with samples of drill core to test the precision and accuracy of the analytic procedures MSA laboratory in Canada. 26 reference analyses were analysed in the samples submitted in 2019. The standards demonstrate suitable precision and accuracy of the

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director



For drill holes from GNDD011 plus unsampled intervals from the 2019 drilling, 17 different multi-element Certified Standard Reference pulp samples (CRM) with known values for Au Ag Fe S Pb Cu and Zn. 7 different CRM's with known values for Au only have been submitted with samples of drill core, RC chips and channel samples to test the precision and accuracy of the analytic procedures of the MSA,ALS and SGS laboratories used. In the results received to date there has been no systematic bias is observed. The standards demonstrate suitable precision and accuracy of the analytic process. A summary of the standard deviations from the expected values for CRM's used is summarised below. Generally, an average of standard deviations close to zero indicates a high degree of accuracy and a low range of standard deviations with a low fail count indicates a high degree of precision.



Challenger Gold Limited ACN 123 591 382 ASX: CEL

Criteria

Issued Capital 1,688m shares 126.7m options 50.5m perf rights

JORC Code explanation

Australian Registered Office Level 1 100 Havelock Street

West Perth WA 6005

Mr Kris Knauer, MD and CEO Mr Sergio Rotondo, Chairman Dr Sonia Delgado, Exec. Director Mr Fletcher Quinn, Non-Exec. Director Mr Pini Althaus , Non Exec Director Mr Brett Hackett Non Exec Director

Directors



Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Contact T: +61 8 6385 2743 E: admin@challengergold.com




Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Contact T: +61 8 6385 2743 E: admin@challengergold.com



Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Contact T: +61 8 6385 2743 E: admin@challengergold.com



Verification of sampling and assaying

- The verification of significant intersections by either independent or alternative company personnel.
- The use of twinned holes.
- Documentation of primary data entry procedures data verification data storage (physical and electronic) protocols.
- Discuss any adjustment to assay data.

Final sample assay analyses are received by digital file in PDF and CSV format. There is no adjustment made to any of the assay values received. The original files are backed-up and the data copied into a cloud-based drill hole database, stored offsite from the project. The data is remotely accessible for geological modelling and resource estimation.

Assay results summarised in the context of this report have been rounded appropriately to 2 significant figures. No assay data have been otherwise adjusted. Replicate assay of 186 coarse reject samples from 2019 drilling has been done to verify assay precision. Original core samples were from the 2019 DD drilling which were analysed by MSA (San Juan preparation and Vancouver analysis). Coarse reject samples were analysed by ALS (Mendoza preparation and Vancouver analysis). The repeat analysis technique was identical to the original. The repeat analyses correlate very closely with the original analyses providing high confidence in precision of results between MSA and ALS. A summary of the results for the 186 sample pairs for key elements is provided below:

	Mean		Median		Std Deviation		
Element	MSA	ALS	MSA	ALS	MSA	ALS	Correlation coefficient
Au (FA and GFA ppm)	4.24	4.27	0.50	0.49	11.15	11.00	0.9972
Ag (ICP and ICF ppm)	30.1	31.1	5.8	6.2	72.4	73.9	0.9903
Zn ppm (ICP ppm and ICF %)	12312	12636	2574	2715	32648	33744	0.9997
Cu ppm (ICP ppm and ICF %)	464	474	74	80	1028	1050	0.9994
Pb ppm (ICP ppm and ICF %)	1944	1983	403	427	6626	6704	0.9997
S (ICP and ICF %)	2.05	1.95	0.05	0.06	5.53	5.10	0.9987
Cd (ICP ppm)	68.5	68.8	12.4	12.8	162.4	159.3	0.9988

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Contact T: +61 8 6385 2743 E: admin@challengergold.com

Criteria	JORC Code explanation	Commentary							
		As (ICP ppm))	76.0	79.5	45.8	47.6	88.1	90.6	0.9983
		Fe (ICP %)	4.96	4.91	2.12	2.19	6.87	6.72	0.9994
		REE (ICP ppm)	55.1	56.2	28.7	31.6	98.2	97.6	0.9954
		Cd values >1000 are se	et at 1000.					•	
		REE is the sum off Ce,	La, Sc, Y. CE	> 500 is	set at 50	0. Below	detection	is set at	zero
		Replicate assay of 192	coarse reject s	amnles f	rom 2021	l drilling	has heen	done to v	erify assay nre

Replicate assay of 192 coarse reject samples from 2021 drilling has been done to verify assay precision. Original core samples were from the 2021 DD drilling which were analysed by SGS Laboratories (San Juan preparation and Lima analysis). Coarse reject samples were prepared and analysed by ALS (Mendoza preparation and Lima analysis). The repeat analysis technique was identical to the original. Except for Mo (molybdenum), the repeat analyses correlate closely with the original analyses providing confidence in precision of results between SGS and ALS. A summary of the results for the 192 sample pairs for key elements is provided below:

		Mean		Medi	an	Std Devia	ation	
								Correlation
Element	count	SGS	ALS	SGS	ALS	SGS	ALS	coefficient
Au (FA and GFA ppm)	192	1.754	1.680	0.432	0.441	20.8	21.5	0.9837
Ag (ICP and ICF ppm)	192	12.14	11.57	0.93	1.03	7085	5925	0.9995
Zn (ICP and ICF ppm)	192	6829	7052	709	685	4.54E+08	5.34E+08	0.9942
Cu (ICP and ICF ppm)	192	203.4	202.9	25.7	24.5	3.30E+05	3.35E+05	0.9967
Pb (ICP and ICF ppm)	192	1768	1719	94.7	91.6	5.04E+07	4.39E+07	0.9959
S (ICP and ICF %)	192	2.23	2.10	0.94	0.87	16.51	15.56	0.9953
Cd (ICP ppm)	192	43.9	42.4	4.1	4.0	19594	18511	0.9956
As (ICP ppm))	192	45.4	45.2	16.0	16.9	10823	9893	0.9947
Fe (ICP %)	189	3.07	3.30	2.38	2.31	4.80	9.28	0.9781
REE (ICP ppm)	192	63.5	72.8	39.4	44.3	3414	4647	0.9096
Mo (ICP and ICF ppm)	192	7.69	1.68	6.74	0.97	85.83	10.33	0.3026

Values below detection were set to half the detection limit

Limit of detection for Fe was exceeded for 3 samples submitted to SGS with no overlimit analysis REE is the sum off Ce, La, Sc, Y. Vaues below detection were set at zero.

Replicate assay of 140 pulp reject samples from the 2022 drill (parts of drill holes GNDD654 and GNDD666) was done to check assay precision. The original pulps were analysed by MSA laboratories (San Juan preparation and Vancouver, Canada analysis). Replicate pulps were analysed by ALS (Lima, Peru). The analytic techniques were identical at both laboratories.

Mean Median Std Deviation

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary										
										Correlation		
		Element	count	SGS	ALS	SGS	ALS	SGS	ALS	coefficient		
		Au (FA ppm)	140	0.27	0.30	0.01	0.02	0.98	1.05	0.9829		
		Ag (ICP ppm)	140	1.16	1.14	0.16	0.16	6.15	6.31	0.9965		
		Zn (ICP ppm)	140	555	565	50	56	2471	2469	0.9996		
		Pb (ICP ppm)	140	92.3	95.4	13.6	13.5	338	351	0.9977		
		S (ICP %)	140	0.64	0.61	0.17	0.17	1.22	1.12	0.9982		
		Fe (ICP %)	140	1.62	1.59	0.64	0.66	1.91	1.88	0.9991		
		CEL have sought to twin and triplicate some of the historic and recent drill holes to check the resexploration. A preliminary analysis of the twin holes indicates similar widths and grades for key assayed. The twin holes are: GNDD003 – DDH34 and 04HD08 GNRC110 – DDH53 GNDD144 – GNDD021 – 05HD39 GNRC107 – GNDD008/008A GNDD206 – DDH54 GNDD421 – GNDD424										
Location of data points	Accuracy and quality of survey used to locate drill holes (collar and down-hole surveys) trench	nearby Argentinian SGM survey point. The collars have been surveyed in POSGAR 2007 zon								one 2 and converte		
	mine workings and other locations used in Mineral Resource estimation.	mark at the entranc	Following completion of the channel sampling, the location of the channel samples is surveyed from a survey mark at the entrance to the underground workings, located using differential GPS. The locations have been surveyed in POSGAR 2007 zone 2 and converted to WGS84 UTM zone 19s.									
	Specification of the grid system used.Quality and adequacy of	The drill machine is design.	The drill machine is set-up on the drill pad using hand-held survey equipment according to the proposed hole design.									
	topographic control.	Diamond core drill hole compass and i surveyed down hole gyroscope down-ho	nclinometer to e using a gyro	ool. RC d	Irill holes avoid m	and dian agnetic in	nond core fluence fro	holes from G om the drill st	NDD391 tring and i	were continuously		
		Ten diamond drill he loss of drilling equip holes, a survey of the	ment. These	are GND	D036, 1	97, 212, 2	283, 376,	423, 425, 439	9, 445 and	d 465. For these		
		All current and prev using DGPS to prov metre precision has	ide topograpi	nic contro	I for the	Project. I	n addition	, AWD3D DT	M model	with a nominal 2.5		

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary
		survey data with 0.1 meter precision is being acquired over the project to provide more detail where required.
Data spacing and distribution	 Data spacing for reporting of Exploration Results. Whether the data spacing and distribution is sufficient to establish the degree of geological and grade continuity appropriate for the Mineral Resource and Ore Reserve estimation procedure(s) and classifications applied. Whether sample compositing has been applied. 	Nominal 80m x 80m, 40m x 80m and 40m x 40m drill spacing is being applied to the drilling to define mineralised areas to Indicated Resource level of confidence, where appropriate. Drilling has been completed to check previous exploration, extend mineralisation along strike, and provide some information to establish controls on mineralization and exploration potential. Samples have not been composited.
Orientation of data in relation to geological structure	 Whether the orientation of sampling achieves unbiased sampling of possible structures and the extent to which this is known considering the deposit type. If the relationship between the drilling orientation and the orientation of key mineralised structures is considered to have introduced a sampling bias this should be assessed and reported if material. 	As far as is currently understood and where practicable, the orientation of sampling achieves unbiased sampling of structures and geology controlling the mineralisation. Some exploration holes have drilled at a low angle to mineralisation and have been followed up with drill holes in the opposite direction to define mineralised domains. For underground channel sampling, the orientation of the sample is determined by the orientation of the workings. Where the sampling is parallel with the strike of the mineralisation, plans showing the location of the sampling relative to the orientation of the mineralisation, weighted average grades and estimates of true thickness are provided to provide a balanced report of the mineralisation that has been sampled. Drilling has been designed to provide an unbiased sample of the geology and mineralisation targeted. In exceptional circumstances, where drill access is restricted, drilling may be non-optimally angled across the mineralised zone.
Sample security	 The measures taken to ensure sample security. 	Samples were under constant supervision by site security, senior technical personnel and courier contractors prior to delivery to the preparation laboratories in San Juan and Mendoza.
Audits or reviews	 The results of any audits or reviews of sampling techniques and data. 	There has not yet been any independent reviews of the sampling techniques and data.

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Section 2 Reporting of Exploration Results

(Criteria listed in the preceding section also apply to this section.)

Criteria

JORC Code explanation

Mineral tenement and land tenure status

- Type reference name/number location and ownership including agreements or material issues with third parties such as joint ventures partnerships overriding royalties native title interests historical sites wilderness or national park and environmental settings.
- The security of the tenure held at the time of reporting along with any known impediments to obtaining a licence to operate in the area.

Commentary

The Hualilan Project comprises fifteen Minas (equivalent of mining leases) and five Demasias (mining lease extensions) held under an farmin agreement with Golden Mining SRL (Cerro Sur) and CIA GPL SRL (Cerro Norte).

Fourteen additional Minas and eight exploration licences (Cateos) have been transferred to CEL under a separate farmin agreement. Six Cateos and eight requested mining leases are directly held. This covers all of the currently defined mineralization and surrounding prospective ground. There are no royalties held over the tenements.

Granted mining leases (Minas Otorgadas) at the Hualilan Project

Name	Number	Current Owner	Status	Grant Date	Area (ha)
Cerro Sur					
Divisadero	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Flor de Hualilan	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Pereyra y Aciar	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Bicolor	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Sentazon	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Muchilera	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Magnata	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Pizarro	5448-M-1960	Golden Mining S.R.L.	Granted	30/04/2015	6
Cerro Norte					
La Toro	5448-M-1960	CIA GPL S.R.L.	Granted	30/04/2015	6
La Puntilla	5448-M-1960	CIA GPL S.R.L.	Granted	30/04/2015	6
Pique de Ortega	5448-M-1960	CIA GPL S.R.L.	Granted	30/04/2015	6
Descrubidora	5448-M-1960	CIA GPL S.R.L.	Granted	30/04/2015	6
Pardo	5448-M-1960	CIA GPL S.R.L.	Granted	30/04/2015	6
Sanchez	5448-M-1960	CIA GPL S.R.L.	Granted	30/04/2015	6
Andacollo	5448-M-1960	CIA GPL S.R.L.	Granted	30/04/2015	6

Mining Lease extensions (Demasias) at the Hualilan Project

Name	Number	Current Owner	Status	Grant date	Area (ha)
Cerro Sur					
North of "Pizarro"	195-152-C-1981	Golden Mining	Granted	29/12/1981	2.42
Mine	193-132-C-1981	S.R.L.	Granteu	29/12/1901	2.42
Cerro Norte					

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary	Commentary				
		South of "Andacollo" Mine	545.208-B-94	CIA GPL S.R.L.	Pending Reconsideration	14/02/1994	1.83
		South of "Sanchez" Mine	545.209-B-94	CIA GPL S.R.L.	Registered	14/02/1994	3.50
		South of "La Toro" Mine	195-152-C-1981	CIA GPL S.R.L.	Granted	29/12/1981	2.42
		South of "Pizarro" Mine	545.207-B-94	Golden Mining S.R.L.	Registered	14/02/1994	2.09

Requested Mining Leases (Minas Solicitados)

Name	Number	Status	Area (ha)
Elena	1124.328-G-2021	Registered	2,799.24
Juan Cruz	1124.329-G-2021	Granted	933.69
Paula (over "Lo Que Vendra")	1124.454-G-2021	Application	1,460.06
Argelia	1124.486-G-2021	Registered	3,660.50
Ana Maria (over Ak2)	1124.287-G-2021	Registered	5,572.80
Erica (Over "El Peñón")	1124.541-G-2021	Application	6.00
Silvia Beatriz (over "AK3")	1124.572-G-2021	Application	2,290.75
Soldado Poltronieri (over 1124188-20,	1124.108-2022	Application	777.56
545867-R-94 and 545880-O-94)			

Mining Lease Farmin Agreements

Name	Number	Transfrred to CEL	Status	Area (ha)
Marta Alicia	2260-S-58	In Process	Granted	23.54
Marta	339.154-R-92	In Process	Granted	478.50
Solitario 1-5	545.604-C-94	In Process	Application	685.00
Solitario 1-4	545.605-C-94	In Process	Registered	310.83
Solitario 1-1	545.608-C-94	In Process	Application	TBA
Solitario 6-1	545.788-C-94	In Process	Application	TBA
AGU 3	11240114-2014	No	Granted	1,500.00
AGU 5	1124.0343-2014	No	Granted	1,443.58
AGU 6	1124.0623-2017	No	Granted	1,500.00
AGU 7	1124.0622-S-17	No	Granted	1,500.00
Guillermina	1124.045-S-2019	No	Granted	2,921.05
El Petiso	1124.2478-71	No	Granted	18.00
Ayen/Josefina	1124.495-I-20	No	Granted	2059.6

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights **Australian Registered Office** Level 1 100 Havelock Street

West Perth WA 6005

Directors

Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary	1				
		Exploration L	icence (Cateo) Farmin	Agreements			
		Name	Number	Transfrred to CEL		Status	Area (h
		-	295.122-R-1989	In process	Re	gistered	1,882.5
		-	338.441-R-1993	In process	G	Granted	2,800.0
		-	545.880-0-1994	In process	Re	gistered	149.99
		-	414.998-2005	Yes	G	Granted	721.90
		-	1124.011-I-07	No	G	Granted	2552
		-	1124.012-I-07	No	Re	gistered	6677
		-	1124.013-I-07	No	G	Granted	5818
		=	1124.074-I-07	No	G	Granted	4484.5
		Exploration L	icence (Cateo) Held (L	Direct Award)			
		Name	Number	Transfrr	ed to CEL	Status	Area (ha)
		-	1124-248G-20	Yes		Current	933.20
		=	1124-188-G-20 (2 z	ones) Yes		Current	327.16
		=	1124.313-2021	Yes		Current	986.41
		-	1124.564-G-2021	Yes		Current	1,521.12
		-	1124.632-G-2022	Yes		Current	4,287.38
		There are no	known impediments to	obtaining the expl	oration lic	enses or op	perating the F
Exploration done by other parties	 Acknowledgment and appraisal exploration by other parties. 	geological mannon-JORC reprior to exploor the second of th	storic sampling has praps, reports, trenching source estimates plus ration by CEL, no work ast 6 km of undergrour workings are likely to sampling have been could drill hole results. His pleted by CEL.	data, underground property examination has been completed workings that particle be incomplete. Compiled and digitise	surveys, ons and ded on the ss through immonly ited as has	drill hole readed student of the complete sample date of the complete sample date of the complete of the compl	sults, geophy dies by multip ce 2006. ed zones at he records of the a geological
			g on or near the Hualil s. The key historical ex				
		- 1995 - 1998	 Lixivia SA channel s Plata Mining Limited Chilean consulting f ing and channel samp 	(TSE: PMT) 33 RC rm EPROM (on be	holes (H	ua- 1 to 33) + 1,500 RC
enger Gold Limited	Issued Capital Australian	mapp Registered Office Dire	•	•		3,	

ACN 123 591 382 ASX: CEL 1,688m shares 126.7m options 50.5m perf rights Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary
		 1999 – Compania Mineral El Colorado SA ("CMEC") 59 diamond core holes (DDH-20 to 79) plus 1,700m RC program 2003 – 2005 – La Mancha (TSE Listed) undertook 7,447m of DDH core drilling (HD-01 to HD-48) Detailed resource estimation studies were undertaken by EPROM Ltd. (EPROM) in 1996 and CMEC (1999 revised 2000) both of which are well documented and La Mancha 2003 and 2006. The collection of all exploration data by the various operators was of a high standard and appropriate sampling techniques intervals and custody procedures were used. Not all the historic data has been archived and so there are gaps in the availability of the historic data.
Geology	 Deposit type geological setting and style of mineralisation. 	Mineralisation occurs in all rock types where it preferentially replaces limestone, shale and sandstone and occurs in fault zones and in fracture networks within dacitic intrusions.
		The mineralisation is Zn-(Pb-Cu-Ag) distal skarn (or manto-style skarn) overprinted with vein-hosted mesothermal to epithermal Au-Ag mineralisation. It has been divided into three phases – prograde skarn, retrograde skarn and a later quartz-rich mineralisation consistent with the evolution of a large hydrothermal system. Precise mineral paragenesis and hydrothermal evolution is the subject of ongoing work which is being used for exploration and detailed geometallurgical test work.
		Gold occurs in native form as inclusions with sulphide (predominantly pyrite) and in pyroxene. The mineralisation commonly contains pyrite, chalcopyrite sphalerite and galena with rare arsenopyrite, pyrrhotite and magnetite.
		Mineralisation is either parallel to bedding in bedding-parallel faults, in veins or breccia matrix within fractured dacitic intrusions, at lithology contacts or in east-west striking steeply dipping siliceous faults that cross the bedding at a high angle. The faults have thicknesses of 1–4 metres and contain abundant sulphides. The intersection between the bedding-parallel mineralisation and east-striking cross veins seems to be important in localising the mineralisation.
		Complete oxidation of the surface rock due to weathering is thin. A partial oxidation / fracture oxidation layer near surface is 1 to 40m thick and has been modelled from drill hole intersections.
Drill hole Information	 A summary of all information material to the understanding of the exploration results including a tabulation of the following information for all Material drill holes: easting and northing of the drill hole collar elevation or RL (Reduced Level – elevation above sea level in metres) of the drill hole collar 	Significant intersections previous reported for historic drill holes, DD drill holes, RC drill holes completed by CEL are detailed in CEL ASX releases: 1 June 2022 (Maiden MRE): https://announcements.asx.com.au/asxpdf/20220601/pdf/459jfk8g7x2mty.pdf and 29 March 2023 (MRE update): https://announcements.asx.com.au/asxpdf/20230329/pdf/45n49jlm02grm1.pdf A cut-off grade of 1 g/t Au equivalent has been used with up to 2m of internal diltion or a cut-off grade of 0.2 g/t Au equivalent and up to 4m of internal diltion has been allowed. No metallurcial or recovery factors have been used in the intersections reported.

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary
	 dip and azimuth of the hole down hole length and interception depth hole length. If the exclusion of this information justified on the basis that the information is not Material and thi exclusion does not detract from the understanding of the report the Competent Person should clearly explain why this is the case. 	is S
Data aggregation methods	In reporting Exploration Results was averaging techniques maximum a minimum grade truncations (eg chigh grades) and cut-off grades a Material and should be stated. Where aggregate intercepts incorporations.	are reported to cut-off grade of a 1.0 g/t Au equivalent and 10 g/t Au equivalent allowing for up to 2m of internal dilution between samples above the cut-off grade and 0.2 g/t Au equivalent allowing up to 10m of internal dilution between samples above the cut-off grade. The following metals and metal prices have been used to report gold grade equivalent (AuEq): Au US\$ 1780 / oz Ag US\$24
	short lengths of high-grade results and longer lengths of low-grade results the procedure used for such aggregation should be stated and some typical examples of such aggregations should be shown in detail. The assumptions used for any reporting of metal equivalent values should be clearly stated.	metallurgical test work completed by SGS Metallurgical Operations in Lakefield, Ontario using a combination of gravity and flotation of a combined metallurgical sample from 5 drill holes. Using data from the interim test results, and for the purposes of the AuEq calculation for drill hole significant intercepts, gold recovery is estimated For the AuEq calculation average metallurgical recovery is estimated to be 94.9% for gold, 90.9% for silver, 67.0% for Zn and 57.8% for Pb. Metal prices used to report AuEq are Au US\$ 1900 / oz, Ag US\$24 /oz, Zn US\$ 4,000 /t and Pb
		(0.578/.9490). Metallurgical test work and geological and petrographic descriptions suggest all the elements included in the metal equivalents calculation have reasonable potential of eventual economic recovery. While Cu and Pb are reported in the table above as they were not yet considered economically significant at the time of the interim metallurgical test results, these metals were not used in the Au equivalent calculation at this early stage of the Project.
		No top cuts have been applied to the reported grades.
Relationship between mineralisation	 These relationships are particular important in the reporting of Exploration Results. 	The mineralisation is moderately or steeply dipping and strikes NNE and ENE. For some drill holes, there is insufficient information to confidently establish the true width of the mineralized intersections at this stage of the exploration program.

Directors

Mr Kris Knauer, MD and CEO

Mr Sergio Rotondo, Chairman

Dr Sonia Delgado, Exec. Director Mr Fletcher Quinn, Non-Exec. Director Mr Pini Althaus , Non Exec Director Mr Brett Hackett Non Exec Director Contact

T: +61 8 6385 2743

E: admin@challengergold.com

www.challengergold.com

Issued Capital

1,688m shares

126.7m options

50.5m perf rights

Australian Registered Office

100 Havelock Street

West Perth WA 6005

Level 1

Challenger Gold Limited

ACN 123 591 382

ASX: CEL

Criteria	JORC Code explanation	Commentary
widths and intercept lengths	 If the geometry of the mineralisation with respect to the drill hole angle is 	Apparent widths may be thicker in the case where the dip of the mineralisation changes and/or bedding-parallel mineralisation intersects NW or ENE-striking cross faults and veins.
	 known its nature should be reported. If it is not known and only the down hole lengths are reported there should be a clear statement to this effect (eg 'down hole length true width not known'). 	Representative cross section interpretations have been provided periodically with releases of significant intersections to allow estimation of true widths from individual drill intercepts.
Diagrams	 Appropriate maps and sections (with scales) and tabulations of intercepts should be included for any significant discovery being reported These should include but not be limited to a plan view of drill hole collar locations and appropriate sectional views. 	Representative maps and sections are provided in the body of reports released to the ASX.
Balanced reporting	 Where comprehensive reporting of all Exploration Results is not practicable representative reporting of both low and high grades and/or widths should be practiced to avoid misleading reporting of Exploration Results. 	All available final data have been reported where possible.
Other substantive exploration data	- Other exploration data if meaningful and material should be reported including (but not limited to): geological observations; geophysical survey results; geochemical survey results; bulk samples – size and method of treatment; metallurgical test results; bulk density groundwater geotechnical and rock characteristics; potential deleterious or contaminating substances.	Specific gravity measurements have been taken from the drill core recovered during the drilling program. These data are used to estimate densities in Resource Estimates. Eight Induced Polarisation (IP) lines have been completed in the northern areas of the Project. Stage 1 surveying was done on 1 kilometre length lines oriented 115° azimuth, spaced 100m apart with a 50m dipole. The initial results indicate possible extension of the mineralisation with depth. Stage 2 surveying was done across the entire field on 1 – 3 kilometre length lines oriented 090°, spaced 400m apart with a 50m dipole. On-going data interpretation is being done as drilling proceeds. Three ground magnetic surveys and a drone magnetic survey have been completed. The results of these data and subsequent geological interpretations are being used to guide future exploration. Metallurgical test results are used to estimate the AuEq (gold equivalent) as detailed above in <i>Data Aggregation</i> and below in <i>Section 3: Metallurgical Factors or Assumptions</i> . The formula used for AuEq is: AuEq (g/t) = Au (g/t) + [Ag (g/t) x (24/1900) x (0.909/0.949)] + [Zn (%) x (40.00*31.1/1900) x (0.670/0.949)] + (Pb (%) x 20.00*31.1/1900) x (0.578/.9490). Point resistivity surveys have been completed east of the Project for the purposes of detecting the presence of groundwater. Three surveys (total of 22 points) have been completed. A water bore has been drilled approximately 4 kilometres to the east of the Project which found water in permeable Quaternary sedimentary deposits above hard-rock basement at 128 metres vertical depth. Testing and

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary
		commissioning of the bore has yet to be completed. Further geophysical test work is planned to determine the extent of the aquifer.
Further work	 The nature and scale of planned further work (eg tests for lateral extensions or depth extensions or large-scale step-out drilling). Diagrams clearly highlighting the areas of possible extensions including the main geological interpretations and future drilling areas provided this information is not commercially sensitive. 	 CEL Plans to undertake the following over the next 12 months Additional resource extension, infill and exploration drilling; Geophysical tests for undercover areas. Structural interpretation and alteration mapping using high resolution satellite data and geophysics to better target extensions of known mineralisation. Field mapping program targeting extensions of known mineralisation. Further metallurgical test work.

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Section 3 Estimation and Reporting of Mineral Resources

(Criteria listed in the preceding section also apply to this section.)

Criteria	JORC Code explanation	Commentary
Database integrity	 Measures taken to ensure that data has not been corrupted by for example transcription or keying errors between its initial collection and its use for Mineral Resource estimation purposes. Data validation procedures used. 	Geological logging completed by previous explorers was done on paper copies and transcribed into a series of excel spreadsheets. These data have been checked for errors. Checks have been made against the original logs an with follow-up twin and close spaced drilling. Only some of the historic drill holes have been used in the Resource Estimate, including the results presented in Section2. Some drill holes have been excluded where the geology indicates that the drill hole is likely mis-located or where the drill hole has been superseded by CEL drilling. For CEL drilled holes, assay data is received in digital format. Backup copies are backed up into a cloud-based file storage system and the data is entered into a drill hole database which is also securely backed up off site.
Cita viaita	Comment on any site visits undertains but he	The drill hole data is backed up and is updated periodically by the CEL GIS and data management team.
Site visits	 Comment on any site visits undertaken by the Competent Person and the outcome of those visits. If no site visits have been undertaken indicate why this is the case. 	The Competent Person has undertaken site visits during exploration. Site visits were undertaken in 2019 and 2020 before COVID-19 closed international travel. Post COVID numerous site visits have undertaken since November 2021. The performance of the drilling program, collection of data, sampling procedures, sample submission and exploration program were initiated and reviewed during these visits.
Geological interpretation	 Confidence in (or conversely the uncertainty of) the geological interpretation of the mineral deposit. Nature of the data used and of any assumptions made. The effect if any of alternative interpretations on Mineral Resource estimation. The use of geology in guiding and controlling Mineral Resource estimation. The factors affecting continuity both of grade and geology. 	The geological interpretation is considered appropriate given the drill core density of data that has been collected access to mineralisation at surface and underground exposures. Given the data, geological studies past and completed by CEL, the Competent Person has a high level of confidence in the geological model that has been use to constrain the mineralised domains. It is assumed that networks of fractures controlled by local geological factors have focussed hydrothermal fluids and been the site of mineralisation in both the prograde zinc skarn and retrograde mesothermal – epithermal stages of hydrothermal evolution. The interpretation captures the essential geometry of the mineralised structure and lithologies with drill data supporting the findings from the initial underground sampling activities. Mineralised domains have been built using explicit wireframe techniques from 0.2 – 0.5 g/t AuEq mineralised intersections, joined between holes by the instruction from the geology and structure. Continuity of grade between drill holes is determined by the intensity of fracturing, the host rock contacts (particularly dacite – limestone contacts) and by bedding parallel faults, particularly within limestone, at the limestone and overlying sedimentary rock contact and within the lower sequences of the sedimentary rocks within 40m of the contact. No alternative interpretations have been made form which a Mineral Resource Estimate has been made.
Dimensions	 The extent and variability of the Mineral Resource expressed as length (along strike or otherwise) plan width and depth below surface to the upper and lower limits of the Mineral 	31 separate domains were interpreted over a strike length of 2.3kms. The domains vary in width and orientation from 2m up to 100m in width. The deepest interpreted domain extends from the surface down approximately 600m below surface.

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Comme	ntary					
	Resource.							
Estimation and modelling techniques	 The nature and appropriateness of the estimation technique(s) applied and key assumptions including treatment of extreme grade values domaining interpolation 	Fe and S	on was made for Au Ag, Zn and Pb being the elements that for pyrite which is of the density for bocks in the Mineral Resource	economic and				
	parameters and maximum distance of extrapolation from data points. If a computer assisted estimation method was chosen include		ous JORC Resource estimates or non-JORC For e to the current Resource estimate. No produc	_				hods
	 a description of computer software and parameters used. The availability of check estimates previous 		mposite length was selected after reviewing the length of 1.54m for samples taken within the	•		rom the drilli	ng which sho	wed
	estimates and/or mine production records and whether the Mineral Resource estimate takes appropriate account of such data. The assumptions made regarding recovery of by-products. Estimation of deleterious elements or other non-grade variables of economic significance		ical analysis was undertaken on the sample co by-domain basis. The domains were then grou were applied in order to reduce the influence ading the high-grade composites too severely. ion of the grade population within each group erratic. The following table shows the top cut out was applied to estimation of Fe and S.	uped by host of extreme va The top-cut valued and selecting	rock and mine alues on the r alues were ch g the value ab	eralisation sty esource estimosen by assen ove which the	le and group nates without ssing the high e distribution	dom
	(eg sulphur for acid mine drainage characterisation).		Group	Au (ppm)	Ag (ppm)	Zn (%)	Pb (%)	Ī
	In the case of block model interpolation the block size in relation to the average sample		Fault Zone hosted (Magnata and Sanchez) and CAL (limestone) hosted	80	300	20	5	i
	spacing and the search employed.		LUT (siltstone) hosted	20	100	5	1	1
	- Any assumptions behind modelling of selective		DAC (intrusive) hosted	15	70	5	1.8	
	mining units.Any assumptions about correlation between variables.		odelling was undertaken in Surpac™ V6.6 softv					
	 Description of how the geological interpretation was used to control the resource estimates. Discussion of basis for using or not using grade 	dimensions were chosen to reflect drill hole spacing and to provide definition for potential mine shorter 10m X dimension was used to reflect the geometry and orientation of the majority of the				id vertical blo ne planning. T	ck	
	 cutting or capping. The process of validation the checking process used the comparison of model data to drill hole data and use of reconciliation data if available 		nes. ariography was carried out using Leapfrog Edg omains for each variable.	e software or	n the two met	re composite	d data from e	ach

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Contact T: +61 8 6385 2743 E: admin@challengergold.com

Criteria	JORC Code explanation	Commentary
		All relevant variables; Au, Ag, Pb, Zn, Fe and S in each domain were estimated using Ordinary Kriging using only data from within that domain. The orientation of the search ellipse and variogram model was controlled using surfaces designed to reflect the local orientation of the mineralized structures.
		An oriented "ellipsoid" search for each domain was used to select data for interpolation.
		A 3 pass estimation search was conducted, with expanding search ellipsoid dimensions and decreasing minimum number of samples with each successive pass. First passes were conducted with ellipsoid radii corresponding to 40% of the complete range of variogram structures for the variable being estimated. Pass 2 was conducted with 60% of the complete range of variogram structures for the variable being estimated. Pass 3 was conducted with dimensions corresponding to 200% of the semi-variogram model ranges. Blocks within the model where Au was not estimated during the first 3 passes were assigned as unclassified. Blocks for Ag, Pb, Zn, Fe and S that were not estimated were assigned the average values on a per-domain basis.
		Validation checks included statistical comparison between drill sample grades and Ordinary Kriging block estimate results for each domain. Visual validation of grade trends for each element along the drill sections was also completed in addition to swath plots comparing drill sample grades and model grades for northings, eastings and elevation. These checks show good correlation between estimated block grades and drill sample grades.
Moisture	 Whether the tonnages are estimated on a dry basis or with natural moisture and the method of determination of the moisture content. 	Tonnage is estimated on a dry basis.
Cut-off parameters	 The basis of the adopted cut-off grade(s) or quality parameters applied. 	The following metals and metal prices have been used to report gold grade equivalent (AuEq): Au US\$ 1900 / oz, Ag US\$24 /oz, Zn US\$ 4,000 /t and Pb US 2,000/t.
parameters		Average metallurgical recoveries for Au, Ag, Zn and Pb have been estimated from the results of Stage 1 metallurgical test work completed by SGS Metallurgical Operations in Lakefield, Ontario using a combination of gravity and flotation combined metallurgical samples as detailed in the Criteria below. For the AuEq calculation average metallurgical recovery is estimated as 94.9% for gold, 90.9% for silver, 67.0% for Zn and 57.8% for Pb.
		Accordingly, the formula used for Au Equivalent is: AuEq (g/t) = Au (g/t) + [Ag (g/t) \times (24/1900) \times (0.909/0.949)] + [Zn (%) \times (40.00*31.1/1900) \times (0.670/0.949)] + (Pb (%) \times 20.00*31.1/1900) \times (0.578/.9490}.
		Based on the break-even grade for an optimised pit shell for gold equivalent, a AuEq cut-off grade of 0.30 ppm is used to report the resource within an optimised pit shell run at a gold price of US\$1,800 per ounce and allowing for Ag, Zn and Pb credits. Under this scenario, blocks with a grade above the 0.30 g/t Au Eq cut off are considered to have reasonable prospects of mining by open pit methods.
		A AuEq cut-off grade of 1.0 ppm was used to report the resource beneath the optimised pit shell run as these blocks are considered to have reasonable prospects of future mining by underground methods.

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria

JORC Code explanation

Commentary

Mining factors or assumptions

Assumptions made regarding possible mining methods minimum mining dimensions and internal (or if applicable external) mining dilution. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider potential mining methods but the assumptions made regarding mining methods and parameters when estimating Mineral Resources may not always be rigorous. Where this is the case this should be reported with an explanation of the basis of the mining assumptions made.

The Resource estimate has assumed that near surface mineralisation would be amenable to open pit mining given that the mineralisation is exposed at surface and under relatively thin unconsolidated cover. A surface mine optimiser has been used to determine the proportion of the Resource estimate model that would be amenable to eventual economic extraction by open pit mining methods. The surface mine optimiser was bult using the following parameters with prices in USD:

- Au price of \$1,800 per oz, Ag price of \$23.4 per oz, Zn price of \$3,825 per tonne and Pb price of \$1,980 per tonne
- Average metallurgical recoveries of 94.9% for Au, 90.9 % for Ag and 67 % for Zn and 57.8 % for Pb.
- Ore and waste mining cost of \$2.00 per tonne
- Unconsolidated cover removal cost of \$0.10 per tonne
- Processing cost of \$10.00 per tonne
- Transport and marketing of \$50 / oz of AuEq (road to Jan Juan then rail to Rosario Port)
- Royalty of \$60 per oz Au, 3% for Ag, Zn and Pb.
- Assumed concentrate payability of 94.1% for Au, 82.9% for Ag, 90 % for Zn and 95 % for Pb.
- 45° pit slopes on the western side of the pit and 55° on the eastern side of the pit

Blocks above a 0.30 g/t AuEq within the optimised open pit shell are determined to have reasonable prospects of future economic extraction by open pit mining and are included in the Resource estimate on that basis. Blocks below the open pit shell that are above 1.0 g/t AuEq are determined to have reasonable prospects of future economic extraction by underground mining methods and are included in the Resource estimate on that basis.

Metallurgical factors or assumptions

The basis for assumptions or predictions regarding metallurgical amenability. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider potential metallurgical methods but the assumptions regarding metallurgical treatment processes and parameters made when reporting Mineral Resources may not always be rigorous. Where this is the case this should be reported with an explanation of the basis of the metallurgical assumptions made.

CEL has completed Stage 1 metallurgical test work on representative composite sample of mineralisation from:

- 1. Two separate composite samples of limestone-hosted massive sulphide (manto) Sample A has a weighted average grade of 10.4 g/t Au, 31.7 g/t Ag, 3.2 % Zn and 0.46 % Pb. Sample B has a weighted average grade of 9.7 g/t Au, 41.6 g/t Ag, 4.0% Zn and 0.48% Pb.
- 2. One dacite (intrusive) composite sample with a weighted average grade of 1.1 g/t Au, 8.1 g/t Ag and 0.10 % Zn and 0.04% Pb.
- 3. One sediment hosted (fine grained sandstone and siltstone) composite sample with a weighted average grade of 0.68 g/t Au, 7.5 g/t Ag, 0.34 % Zn and 0.06 % Pb.
- 4. One oxidised limestone (manto oxide) composite sample with a weighted average grade of 7.0 g/t Au, 45 g/t Ag, 3.7% Zn and 0.77% Pb.

Gravity recovery and sequential flotation tests of the higher-grade limestone hosted mineralisation involved;

- 1. primary P80 = 51 micron primary grind,
- 2. gravity recovery,
- 3. Pb-Cu followed by Zn rougher flotation,

Challenger Gold Limited ACN 123 591 382 ASX: CEL **Issued Capital** 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary
		4. p80 = 29 micron regrind of the Zn rougher concentrate,
		5. two re-cleaning stages of the Pb/Cu rougher concentrate,
		6. four re-cleaning Sages on the Zn rougher concentrate, and
		7. additional gravity recovery stages added to the Zn Rougher concentrate
		This results in the following products that are likely to be saleable
		- Au-Ag concentrate (118 g/t Au, 286 g/t Ag) with low deleterious elements,
		- Pb concentrate (65% Pb, 178 g/t Au, 765 g/t Ag) with low deleterious elements, and
		- Zn concentrate (51% Zn, 10 g/t Au, 178 g/t Ag) with low deleterious elements, relatively high Cd, but at a
		level that is unlikely to attract penalties.
		- tailing grades of 2 to 3 g/t Au which respond to intensive cyanide leach with recoveries of 70-80% of any
		residual gold and silver to a gold doré bar.
		Two intensive leach tests of Au-Ag concentrate to doré have been completed using a representative samp
		the Au-Ag concentrate. One split of the sample was finely ground to p80 of 16.7 μm and the second split
		finely ground to p80 of 40 μm. The 16.7 μm sample returned a recovery of 96.0% Au and the 40 μm samp
		returned a recovery of 92.8% Au. These results provide an option to eliminate concentrate transport costs
		increase payability for the Au-Ag concentrate.
		Gravity recovery and flotation tests of the intrusive-hosted mineralisation involved;
		1. primary P80 = 120-80 micron primary grind,
		2. gravity recovery,
		3. single stage rougher sulphide flotation,
		4. P80 = 20-30 micron regrind of the rougher concentrate (5-10% mass),
		5. one or two re-cleaning stages of the Au-Ag Rougher concentrate
		At primary grind of p80 = 76 micron and regrind of p80 = 51 micron an Au-Ag concentrate can be produce
		grading 54 g/t Au and 284 g/t Ag with total recoveries of 97% (Au) and 85% (Ag).
		One test of a sediment hosted composite sample (5-10% of the mineralisation at the Project) was a repeat
		the testing done on the intrusive-hosted mineralisation. This produced an Au-Ag concentrate grading 23.6
		Au and 234 g/t Ag at total recoveries of 85% (Au) and 87% (Ag). Further test work is likely to be done as p
		of more detailed studies. It is likely that the concentrate produced from the sediment-hosted mineralisati
		will be combined with the Au-Ag concentrate from the limestone and intrusive-hosted mineralisation.
		Applying recoveries of 70% for both gold and silver to the various concentrate tailings components
		where leaching is likely to be undertaken during production generates recoveries of:
		• 95% (Au), 93% (Ag), 89% (Zn), 70% (Pb) from the high-grade skarn (manto) component of the mineralisate
hallenger Gold Limited	Issued Capital	stralian Registered Office Directors Contact

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005

Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria	JORC Code explanation	Commentary	
		 96% (Au) and 88% (Ag) from the intrusion-hosted component of the mineralisation; 85% (Au) and 87% (Ag) from the sediment-hosted component of the mineralisation; 	
		An intensive cyanide leach test of oxide (limestone and dacite hosted mineralisation has produced recover of 78% (Au) and 64% (Ag) which is expected to be recovered into gold doré bar. While the oxide component the mineralisation comprises only a small percentage of the Hualilan mineralisation its lies in the top 30-40 metres and would be mined early in the case of an open pit operation.	
		Based on the test work to date and the proportions of the various mineralisation types in the current geological model, it is expected that overall average recoveries for potentially saleable metals will be: - 94.9% Au, - 90.9% for Ag - 67.0% for Zn and - 57.8% for Pb As further results are obtained, these assumptions will be updated.	
		Additional Stage 2 work involving column testing of low-grade material, improved recovery of Zn in lower grade mineralisation, comminution and variability testing, blended test work, and pilot plant testing is ongoing and planned.	
Environmental factors or assumptions	- Assumptions made regarding possible waste and process residue disposal options. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider the potential environmental impacts of the mining and processing operation. While at this stage the determination of potential environmental impacts particularly for a greenfields project may not always be well advanced the status of early consideration of these potential environmental impacts should be reported. Where these aspects have not been considered this should be reported with an explanation of the environmental assumptions made.	It is considered that there are no significant environmental factors which would prevent the eventual extractic gold from the project. Environmental surveys and assessments have been completed in the past and will form part of future pre-feasibility studies.	
Bulk density	- Whether assumed or determined. If assumed the basis for the assumptions. If determined	CEL has collected specific gravity (SG) measurements from drill core, which have been used to estimate block densities for the Resource estimate.	

Mr Kris Knauer, MD and CEO

Mr Sergio Rotondo, Chairman

Dr Sonia Delgado, Exec. Director Mr Fletcher Quinn, Non-Exec. Director Mr Pini Althaus , Non Exec Director Mr Brett Hackett Non Exec Director T: +61 8 6385 2743

E: admin@challengergold.com

www.challengergold.com

1,688m shares

126.7m options

50.5m perf rights

Level 1

100 Havelock Street

West Perth WA 6005

ACN 123 591 382

ASX: CEL

С

Criteria JORC Code explanation


the method used whether wet or dry the frequency of the measurements the nature size and representativeness of the samples.

- The bulk density for bulk material must have been measured by methods that adequately account for void spaces (vugs porosity etc) moisture and differences between rock and alteration zones within the deposit.
- Discuss assumptions for bulk density estimates used in the evaluation process of the different materials.

Commentary

Within the mineralised domains there are 956 SG measurements made on drill core samples of 0.1 - 0.2 metres length. Measurements we determined on a dry basis by measuring the difference in sample weight in water and weight in air. For porous samples, the weight in water was measured after wrapping the sample so that no water enters the void space during weighing.


In oxidised and partially oxidised rocks, SG clusters around an average of 2.49 g/cc (2,490 kg/m3) which is independent of depth. A density of 2,490 kg/m3 has been used for oxidised, fracture oxidised and partially oxidised blocks.



In fresh rock samples, a regression model for block density determination has been made by plotting assay interval Fe (%) + S (%) from the interval where the SG measurement was made against the SG measurement. Fe and S are the two elements that form pyrite which is the mineral that is commonly associated with gold and base metal mineralisation at Hualilan. SG plotted against (Fe+S) follows a linear trend within the mineralised domains for oxide and fresh rock as shown below.

Challenger Gold Limited ACN 123 591 382 ASX: CEL

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus , Non Exec Director
Mr Brett Hackett Non Exec Director



Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director

Criteria JORC Code explanation Commentary Discussion of Where appropriate a statement of the relative There is sufficient confidence in the data quality drilling methods and analytical results that they can be relied accuracy and confidence level in the Mineral upon. The available geology and assay data correlate well. The approach and procedure is deemed appropriate relative accuracy/ Resource estimate using an approach or given the confidence limits. The main factors which could affect relative accuracy are: confidence procedure deemed appropriate by the domain boundary assumptions Competent Person. For example the application orientation of statistical or aeostatistical procedures to grade continuity quantify the relative accuracy of the resource top cut. within stated confidence limits or if such an Grade continuity is variable in nature in this style of deposit and has not been demonstrated to date and closer approach is not deemed appropriate a spaced drilling is required to improve the understanding of the grade continuity in both strike and dip directions. It qualitative discussion of the factors that could is noted that the results from the twinning of three holes by La Mancha are encouraging in terms of grade affect the relative accuracy and confidence of repeatability. the estimate. The deposit contains very high grades and there is need for the use of top cuts. The statement should specify whether it relates No production data is available for comparison. to global or local estimates and if local state the relevant tonnages which should be relevant to technical and economic evaluation. Documentation should include assumptions made and the procedures used. These statements of relative accuracy and confidence of the estimate should be compared with production data where available.

Challenger Gold Limited ACN 123 591 382 ASX: CEL

Issued Capital 1,688m shares 126.7m options 50.5m perf rights Australian Registered Office Level 1 100 Havelock Street West Perth WA 6005 Directors
Mr Kris Knauer, MD and CEO
Mr Sergio Rotondo, Chairman
Dr Sonia Delgado, Exec. Director
Mr Fletcher Quinn, Non-Exec. Director
Mr Pini Althaus, Non Exec Director
Mr Brett Hackett Non Exec Director